

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 75-33  
LOCATION C 7 1/2 - S 1/2 - T 14 N  
SEC. 10 TWP. 15 RGE. 14

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Bolberger  
Operator Rudy G. Herman Address Box 662, Russell Kans.  
Field \_\_\_\_\_ County Russell  
Total Depth 3240 Feet.  
Plugging Contractor G-M Casing Pulling Co  
Plugging Contractor's License No. 11  
Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 3/4" @ 750' c.w.c. 5 1/2" @ 3238'  
w/ 75 st cem. Stage collar @ 2400' w/ 75 st cem.  
top plug 2390' top perf. 2366'. Chat to 2355'  
and 5 st cem. Shut off and pulled 5 1/2" casing  
mud to 260' rock bridge and 20 st cem.  
mud to 35' rock bridge and 10 st cem to  
base of cellar

Warren G. Harner  
District Conservation Agent

Date Nov 10, 1954

FILED  
STATE OF

CONSERVATION

**PLUGGING**  
WELL SEC 10 T 15 R 14W  
BOOK PAGE 79 LINE 33

11-12-54