


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 6-4

LOCATION NW NE NE

SEC. 10 TWP. 15 RGE. 14

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A-4 Lease Flegler X-10 UNK

Operator Natl Coop Refg Assn Address Wichita, Kans

Field Hall Gurney Trapp County Russell

Total Depth 3265 Feet.

(Describe briefly the manner in which the well was plugged)

15" 41', 12" 337', 10" 744', 8" 2522', 7" 3137,

All pipe pulled except 554' of 10".

Hole pumped full of mud by Halliburton - set wood plug
at 190', pumped in 25 sax cement through tubing at 190',
pumped in 10 sax Halcogel, set wood plug at 45' and run
10 sax cement at 45', set woodplug at 15', rock bridge
and 10 sax cement to bottom cellar.

5-22-50

PLUGGING
 WILE SEC 10 T 15 R 14
 BOOK PAGE 6 LINE 4

[Signature]
 District Conservation Agent
 Date 5-17-50