

8

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 6-39
LOCATION NE¹/₄ SE¹/₄ NE.
SEC. 10 TWP. 15 RGE. 14 W.

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease F. Hughes

Operator Bennett & Roberts Drilling Co. Address Russell, Kans.

Field _____ County Russell

Total Depth 3225' Feet.

Plugging Contractor Miller Casing Pulling Co.

Plugging Contractor's License No. 12

Address Box 711 Slick Bend, Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 660' cased 350 sp. - 5 1/2" set @ 3209' cased 225 sp. Baker plug set @ 2332' Perforated from 2325' to 2332'. Chok back to 2310' & 5 sp. cem. w/ dump bailer. Shot 5 1/2" off @ 2100' & pulled some & filled w/ heavy mud to 300' from top, set plug rock bridge & 20 sp. cem. w/ bailer. Mud to 35' from top, set plug rock bridge & 10 sp. cem. to base of cellar.

Milton G. Gahandt
District Conservation Agent

Date 10-13-55

PLUGGING
FILE SEC. 10 T. 15 R. 14 W.
BOOK PAGE 6 LINE 39

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1955
CONSERVATION DIVISION
WICHITA, KANSAS
10-17-55