

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 41-9

LOCATION SE-NW-5W

SEC. 10 TWP. 15 RGE. 14W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease Boxberger "A"

Operator N.C.R.A. Address 305 Rule Bldg. Wichita Kans.

Field _____ County Russell

Total Depth 3241 Feet.

Plugging Contractor N.C.R.A.

Plugging Contractor's License No. _____

Address 305 Rule Bldg. Wichita Kans.

(Describe briefly the manner in which the well was plugged)

No surface pipe. 5 1/2" casing set 3238 w/ 75 st Cem.
Plugged back to 3190' Counsel to 3182' Plug
set 365' Hole in casing Cem with 325 st
Cem. Cement Circulated behind 5 1/2" casing.

Hooked up pumps. Casing would take fluid
squeezed 5 1/2" with 100 st Cem. Leaving pipe
filled with Cem. from 365' plug to surface
with Cem. Halliburton Cem. Co.

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1954

Warren W. Horner
District Conservation Agent

Date July 8, 1954

PLUGGING
FILE SEC 10 T 15 R 14W
BOOK PAGE 41 LINE 9

CONSERVATION DIVISION
Wichita, Kansas