

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 93-6

LOCATION SW-SW-SW

SEC. 16 TWP. 16 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Anton C. Redetzke

Operator Duclair Oil & Gas Co Address Box #557 Chase-Kans.

Field _____ County Barton

Total Depth 3310 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 11 ft. Circulated with cement.
5 1/2" casing set at 3306 ft & cemented - Last Hole in
trying to repair well - 5 1/2" casing fractured at 1474 ft.
All casing left in Well - Pumped in 500 sacks
of cement - Filling hole from 1474 ft - to the
surface with cement - both inside & outside of
the 5 1/2" casing - Cement Pumped in
by Halliburton Oil Well-Cementing Co

STATE CORPORATION COMMISSION
4-21-51
APR 21 1951

CONSERVATION DIVISION
Wichita, Kansas
C. W. Stough
District Conservation Agent

Date 4-18-51

PLUGGING
TWP 16-16-11W
23-6