

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-185-21,362-0000

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Big J Production Co., Inc. & Quadel Energy

Complete Address 427 N. St Francis, Wichita, Kansas 67202

Lease Name Cornwell Well No. 1

Location NW NE Sec. 3 Twp. 24 Rge. 15 (~~East~~) (West)

County Stafford Total Depth 4204'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Leben Drilling Co., Inc. and Sun Oilwell Cementing, Inc.

Address 210 Petroleum Bldg., Wichita, Ks. License No. \_\_\_\_\_

Operation Completed: Hour: 10:45 AM Day: 3 Month: September Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows: 8-5/8"-300'-circ. Top Anhydrite 945'

Hole circulated and filled with mud. 60 sacks cement pumped through drill pipe at 600'. 40 sacks cement pumped through drill pipe at 310'. Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement. Mousehole cemented with 10 sacks cement.

9-9-81

Cement used: 50-50 Pozmix w/4% gel and 3% CC.

RECEIVED  
STATE CORPORATION COMMISSION

SEP - 9 1981

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Conservation Division Agent

DATE 10-28-81

INV. NO. 8071 W