

2 040492

4-28

15-095-00009-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

SEC. 31, T 30 S, R 8 W&E

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Messenger Well # A-1

Operator: Pickrell Drilling Co., Inc.

County Kingman 145.96

Name & Address 110 N. Market, #205

Well Total Depth 4491 feet

Wichita, KS 67202

Conductor Pipe: Size feet

316-262-8427

Surface Casing: Size 8-5/8 feet 160'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Company Tools License Number

Address

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Jack Gurley

(company name) Pickrell Drilling (phone)

were: 4-1/2" 4423' - perfs 4360-70' & 4380-90' - CIBP 4260' - casing backed off @ 1134'

10 sx 1417' - 35 sx 1175' - 35 sx 800' - circ 300' - 0

Plugging Proposal Received by Warren Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 17:30 Day: 28 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 2-3/8" tubing was run to 1370' inside the 4-1/2" casing where

10 sx cement was spotted - the tubing was pulled to 1175' where 35 sx of cement

was spotted to fill and cover to top of the 4-1/2" casing - the tubing was pulled

to 800' and another 35 sx of cement was spotted - the tubing was pulled to 300'

where cement was circ to surface

RECEIVED  
MAY 8 1989  
5-8-89

Remarks: Allied #928 60/40 poz 2% gel

CONSERVATION DIVISION

(if additional description is necessary, use BACK of this form)

INVOICED

DATE 5-10-89

Signed [Signature] (TECHNICIAN)

INV. NO. 24709

4-28