

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15176-00-00  
Spot: N2NWSE - Sec/Twnshp/Rge: 17-16S-11W  
2310 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: EDWARD OESER Well Number: 4  
County: BARTON Total Vertical Depth: 3292 feet

Operator License No.: 4252  
Op Name: KAHAN AND ASSOCIATES, INC  
Address: PO BOX 700780  
TULSA, OK 74170

Production Casing Size: 5.5 feet: 3289 250 SX CMT  
Surface Casing Size: 10.75 feet: 141 125 SX CMT

*106 99*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2003 1:00 PM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID M. WILSON Company: KAHAN AND ASSOCIATES, INC. Phone: (918) 492-9797

Proposed Plugging Method: Ordered 560 sxs 60/40 pozmix - 6% gel - 600# hulls.  
Emergency plugging with rig over hole.  
Casing parted at 906'. Heavy drilling mud at 2600'.  
Perfs at 3022' - 3028'.

Plugging Proposal Received By: PAT STAAB WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/18/2003 6:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Chase Well Service RIH hole with tubing to 2523'.  
Copeland rigged up to tubing and pumped 50 sxs 60/40 pozmix with 200# hulls mixed in.  
Pulled tubing to 1507' and pumped 50 sxs 60/40 pozmix with 100# hulls.  
Pulled all tubing to dig out 10' cellar for backside of 10 3/4" casing.  
Ran back in hole with tubing to 900' and pumped 225 sxs cement with 300# hulls to circulate cement to surface.  
Pulled tubing and tied onto casing and pumped 100 sxs 60/40 pozmix.  
Max. P.S.I. 300#. S.I.P. 100#. S.I.P would slowly leak off - cement was leaking out of 10 3/4" below well head.  
Job completed.

RECEIVED

JUN 26 2003  
6:26-03  
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING-TICKET #22593.

Plugged through: TBG

District: 04

Signed *Pat Staab*  
(TECHNICIAN)

INVOICED

6-26-2003

JUN 24 2003

SINCLAIR PRAIRIE OIL CO #4 E OESER

17-16-11W  
NL NW SE

Contr.

BARTON County

E 1839 Comm 5-26-41 Comp. 6-6-41 IP

66 BOPD  
30% WTR

Tops	Depth	Datum
TOP	2625	
LANS	2973	
CONG	3279	
ARB	3289	
TD	3292	

Casing  
10" 141  
5" 3289  
PB 3287  
Shot 6/3270-75: 30/3262-69  
12/3262-67: A/2000  
Pmp 125 BO/7½ hr

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

WANDA