

4-28

E11-520

6 061844

API NUMBER 15- 009-19166-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, SEC. 17, T. 16 S, R. 11 W/EX

2970 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5310

Lease Name Ney Well # 1 SWD

Operator: Four Way Operating Inc.

County Barton

Name & Address: Box 698

Well Total Depth 3,310 feet

Great Bend, Ks. 67530

Conductor Pipe: Size 8 5/8 feet 21'

Surface Casing: Size feet

Abandoned Oil Well Gas Well Input Well X SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698, Great Bend, Ks. 67530

Company to plug at: Hour: 9:30AM Day: 28 Month: April Year: 19 89

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: Order 100 sks common, 400 sks 60/40 Poz 8% Gel 3% Cal C1 5 sks Hulls

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1989
5-17-89
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30PM Day: 28 Month: April Year: 19 89

ACTUAL PLUGGING REPORT
Conductor pipe 8 5/8" set at 21'
w/10 sks. 5 1/2" set at 3202' w/90 sks. Top perf at 2790'. Plugged bottom w/sand and 5 sks cement
to 2740'. Shot pipe three times and recovered 835'. Pumped in 1050' d 2 1/2" tubing 50 sks common cement
followed w/125 sks cement to surface. Pulled tubing and hooked onto 5 1/2" casing and pumped
50 sks cement w/300 psi. 8 5/8" cement to surface.

Remarks: B. J. Titan

(If additional description is necessary, use BACK of this form.)

INVOICED
If (old) observe this plugging.

DATE 5-22-89

Signed Gilbert G. Scheck (TECHNICIAN)

INV. NO. 24890

Gilbert G. Scheck

JUL 11 1989