

4-060803

API Number: 15-009-21,478 - 0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

12-19

NE SE NE /4 SEC. 17, 16 S, 11 W  
3630 feet from S section line  
330 feet from E section line

Operator license# 4252

Lease: Burmeister Well # 1

Operator: Kahan & Associates, Inc.

County: Barton

Address: P.O. Box 700780  
Tulsa, OK 74170

Well total depth 3308 107.51 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 493 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing and Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 11:00 A.M. Day: 19 Month: December Year: 1995

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage, Inc. Phone: 316-938-2943

Were: Order 230 sxs 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 3:00 P.M., Day: 19, Month: December, Year: 1995

Actual plugging report: 8 5/8" to 493' with 275 sxs. 5 1/2" to 3307' with 150 sxs. Perfs at 3301' - 3303'. Sanded to 3250' and spotted 5 sxs cement with dump bailer. Shot casing loose at 2400' and pulled to 1400'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 725' and pumped 35 sxs cement with 200# hulls. Pulled casing to 400' and circulated cement to surface with 50 sxs cement with 100# hulls. Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD

Bottom plug(in place): YES X, CALC, NO

Plugged through TUBING, CASING X. Elevation: 1841 GL

If did not observe the plugging.

STATE CORPORATION COMMISSION  
12-26-95  
Any plug: YES X NO  
Dakota plug: YES X NO  
Signature: Herb Deines  
Agent

INVOICED

DATE 1-5-96

INV. NO. 44417