

4-090491

7-30

10
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-24,520-0800

NE NW SW /4 SEC. 16, 16 S, 11 W
2310 feet from S section line
4290 feet from E section line

Operator license# 9911

Lease Sauber well # 1

Operator: Har-Ken Oil Company

County Barton

109.68

Address: 2932 NW 122nd.
Unit 15
Oklahoma City, OK 73120

Well total depth 3375 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 386 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: L.D. Drilling, Inc. License# 6039

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 28 Month: July Year: 92

Plugging proposal received from: Greg Davidson

Company: L.D. Drilling, Inc. Phone:

Were: Spot plugs through drill pipe with heavy mud between all plugs.
1st. plug @ 3325 feet with 20 sacks.
2nd. plug @ 720 feet with 20 sacks.
3rd. plug @ 435 feet with 90 sacks.
4th. plug @ 40 feet with 10 sacks.
Rate hole: 15 sacks.

Plugging Proposal Received by: Ed Schumacher - P.I.R.T. III
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:00A.M., Day: 30, Month: July, Year: 92

Actual plugging report: Hole reported plugged as above.
Order 155 sx. 60/40 pozmix with 6% gel. and 1 sx. celloflake or flocele.

Remarks: Cemented by: Halliburton Cementing Company
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO
Plugged through TUBING , CASING . Elevation: 1860 ft

RECEIVED
STATE CORPORATION COMMISSION
9-24-92
SEP 24 1992
CONSERVATION DIVISION
Wichita, Kansas

I did observe the plugging. Ed Schumacher

INVOICED
DATE 9-29-92
INV. NO. 36260

(agent)