

4-080207

2-28

15-009-19181-0000

TO:

API number: 10-8-43

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW NE /4 SEC. 19, 16S, 11 W  
4620 feet from S section line  
1980 feet from E section line

Operator license# 5088

Lease A. A. Redetzke well # 3

Operator: John Jay Darrah, Jr.

County Barton

Address: 225 N. Market Suite 300  
Wichita, Kansas 67202

Well total depth 3364 feet 109.33  
Conductor Pipe: inch @ feet  
Surface pipe 8 5/8 Inch @ 322 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: D S & W Well Servicing, Inc. License# 6901

Address: P. O. Box 231, Claflin, Kansas 67525

Company to plug at: Hour: PM Day: 28 Month: February Year: 1997

Plugging proposal received from: Mr. Strube

Company: D S & W Well Servicing, Inc. phone:

Were: 5 1/2" casing set at 3354' with 125 sx. CIBP set at 3300'. Perfs at 3140' to 3238'. Sand to 3280' and bail dump 5 sx cement. Pull casing to 1475' and pump 105 sx 60/40 poz, 10% gel, 300# hulls. Pull to 800' and pump 40 sx 60/40 poz, 10% gel, 200# hulls. Pull to 450' and pump 25sx 60/40 poz, 10% gel. Pull to 200 and pump 40 sx 60/40 poz, 10% gel. Pull casing and top off with 25 sx 60/40 poz, 10% gel.

RECEIVED  
KANSAS CORP COMM  
3-4-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [XXX], None [ ]

Completed: Hour: 2:30 PM, Day: 28, Month: February, Year: 1997

Actual plugging report: Parted 5 1/2" casing. Perfed at 1474', 800' and 450'. Ran tubing to 3300'. Pumped 15 sx gel followed with 50 sx 60/40 poz, 10% gel with 300# hulls. Pulled tubing to 1475. Pumped 125 sx 60/40 poz, 10% gel with 200# hulls, circ cement. Pulled tubing and topped 5 1/2" casing off with 20 sx 60/40 poz, 10% gel. Pumped 35 sx 60/40 poz, 10% gel down backside, 400# shut in pressure

Remarks:  
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING Elevation: 1902 GL

did not [ ] observe the plugging.

Bruce D. Basye  
(agent)

Form CP-2/3

INVOICED

DATE 3-5-97

INV. NO. 47694

2-28