

4-060755

15-009-19244-0000

TO: 10-9  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 3-03-47

SW SW SW        / 4 SEC. 19, 16 S, 11 W  
330 feet from S section line  
4950 feet from E section line

Operator license# 6883

Lease: Hoffman Well # 7

Operator: Robinowitz Oil Company

County: Barton

Address: 7130 South Lewis  
Suite #910  
Tulsa, OK 74136

Well total depth 3380 <sup>109.85</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 778 feet

Aband. oil well X, Gas well       , Input well       , SWD       , D & A       

Plugging contractor: Co Tools License# -

Address:       

Company to plug at: Hour: 10:00 A.M. Day: 9 Month: October Year: 1995

Plugging proposal received from: Darrell Kelso

Company:        Phone: 316-938-2943

Were: Order 500 sxs 60/40 posmix - 10% gel and hulls.  
Plug through tubing.  
Operator working on well. Developed casing problems below 1000'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[    ], None[    ]

Completed: Hour: 11:00 A.M., Day: 9, Month: October, Year: 1995

Actual plugging report: 10 3/4" to 778'. 5 1/2" to 3367' with 50 sxs. Perfs from 3359' - 3371'. Operator had sanded to 3345'. Perforated at 350'. Ran tubing to top of casing problem at 994'. Pumped 50 sxs neat cement - on vacuum - and 150 sxs cement with 450# hulls. Pulled tubing to 500'. Pumped 110 sxs cement with 300# hulls with cement to surface in casing and annulus. Pulled tubing with cement down 5'. No pressure due to hanger on casing.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD        BAD X Any plug: YES X NO       

Bottom plug(in place): YES       , CALC X, NO        Dakota plug: YES X, NO       

Plugged through TUBING X, CASING       . Elevation: 1921 GL

I did[ X ] / did not[    ] observe the plugging.

Herb Deines  
AA (agent)  
Form CP-2/3

INVOICED

DATE 10-27-95  
INV. NO. 43884