

2-25

4-061054

15009-19245-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 4-14-53
N2 SE NE /4 SEC. 19 , 16 S, 11 W
3630 feet from S section line
660 feet from E section line

Operator license# 5088

Lease Redetzke Well # 6

Operator: John J. Darrah, Jr.

County: Barton 108.51

Address: 225 N. Market - Suite #300
Wichita, Kansas 67202

Well total depth 3339 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 773 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 9:00 A.M. Day: 25 Month: February Year: 1997

Plugging proposal received from: Kent Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Order 235 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 3:30 P.M., Day: 25, Month: February, Year: 1997

Actual plugging report: 8 5/8" to 773' w/375 sxs. 5 1/2" to 3332' w/100 sxs. B.P. at 3000'.
Perfs at 2900'. Sand to 2850' and spot 5 sxs cement with dump bailer. Shot casing loose
at 2115' and pulled to 1475'. Mixed and pumped 105 sxs with 300# hulls. Pulled casing to
800' and pumped 40 sxs cement with 200# hulls. Pulled casing to 450' and circulated cement
with 85 sxs cement. Pulled casing with cement in cellar.

1997 MAR 12 11:23 AM
KANSAS RECORDS
3-12-97

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: 1900 GL

I did not observe the plugging.

Herb Deines
(agent)

INVOICED
DATE MAR 12 1997
INV. NO. 47740

Form CP-2/3