

2 040310

4-1-87

00648-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-~~00000000~~
NE SW NW, SEC. 33, T 30 S, R 8 W/X

3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6196

Lease Name Duckworth Well # 1

Operator: Sun Exploration & Prod. Company

County Kingman 145.60

Name & Address 525 Central Park Drive

Well Total Depth 4480 feet

Oklahoma City, OK 73105

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number 5429

Address Attica, KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from J.D. Robinson

(company name) Sun Exploration (phone) _____

were: Set C.I.B.P. at 4300' and two sacks. Circulate top 400'.

4476' of 5 1/2"

400' Hole

Perf. 4340-57

4378-4386

Plugging Proposal Received by Steve Van Gieson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 Day: 1 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT Rods and tubing were pulled from the well. A C.I.B.P.

was set at 4320 to cover off the perforation. The C.I.B.P. was capped with two sacks of cement through a dump bailer. Tubing was run back into the hole and rotary mud was

circulated to surface. Halliburton then tied into the 5 1/2" casing and pumped 150

sacks of Class "A" cement and circulated up the backside

RECEIVED

STATE CORPORATION COMMISSION

APR 7 1987 4-7-87

Remarks: Halliburton #082012 Mx 100#

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(did) observe this plugging.

DATE 4-8-87

Signed [Signature] (TECHNICIAN)

INV. NO. 14527