

15-167-00317-00-01

6-28 4-041588

E-13,149-0002

API number: 15-167-00317

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NW /4 SEC. 09, 12 S, 15 W
2970 feet from S section line
2970 feet from E section line

Operator license# 5259 Lease Brundage well # 1

Operator: Mai Operations County Russell

Address: Box 33 Well total depth 3148 feet
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 272 feet
w/135 sxs.

102.31

Aband. oil well ____, Gas well ____, Input well X, SWD ____, D & A ____

Plugging contractor: Halliburton Cementing License# _____

Address: Hays, Kansas 67601

Company to plug at: Hour: 11:00A.M Day: 28 Month: June Year: 94

Plugging proposal received from: Allen Banger

Company: Halliburton Cementing Phone: _____

Were: 5 1/2" casing set at 3148' w/75 sxs. cement. Perf. at 2845' - 2900'. D.V. Anhy. at 650' w/365 sxs. Squeeze at 650' w/150 sxs. at 400' w/100 sxs. Holes in casing at 2200' - 2800' squeeze w/300 sxs. T.O.C. at 2710'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30P.M., Day: 28, Month: June, Year: 94

Actual plugging report: Plug bottom with sand to 2755' plus 50' of cement on sand. 5 1/2" casing R.I.H. with T. to spot 75 sxs. cement. Pulled tubing to 1200' - spot 75 sxs. cement to circulate at surface. Pulled tubing and squeezed 50 sxs. cement down casing. Max. P.S.I. 400#. 8 5/8" S.P. - cemented at prior date.

Remarks: Halliburton Cementing
Condition of casing(in hole): GOOD ___ BAD X Anhy. plug: YES X NO ___
Bottom plug(in place): YES X, CALC ___, NO ___ Dakota plug: YES X, NO ___
Plugged through TUBING X, CASING ___. Elevation: _____ GL

I did observe the plugging.

Thomas L. Hamill RECEIVED STATE CORPORATION COMMISSION

INVOICED
DATE JUL 06 1994
INV. NO. 40763

(agent) HO.
JUN 30 1994
Form CP-2/3 CONSERVATION DIVISION
Wichita, Kansas