

10-22

187

To: 1 090222  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-093-21,217-0000  
SE NE SW, SEC. 22, T. 24 S, R. 36 W/E  
1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5363

Lease Name Tysor Well # 1  
County Kearny  
Well Total Depth 5075 164.94 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1588

Operator: BEREXCO INC.  
Name & Address P.O. Box 723  
Hays, KS 67601

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BEREXCO License Number 5363

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 2:30 p.m. Day: 22 Month: 10 Year: 19 92

Plugging proposal received from Mark

(company name) BEREXCO (phone) 913-628-6101

well: 4 1/2" at 5074' w/175 sx cement, PBTD 5012', Perfs at 4784-90'

1st plug set CIBP at 4730' and dump 2 sx cement on top,

2nd plug pump 50 sx cement at stub,

3rd plug pump 50. sx cement at 1610',

4th plug pump 40 sx cement at 800', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:15 p.m. Day: 22 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4730' with 2 sx cement on top,

2nd plug shot pipe at 2450' and spotted 30 sx cement,

3rd plug pulled to 1610' and pumped 50 sx cement,

4th plug pumped 40 sx cement at 800',

5th plug pumped 10 sx cement at 40'. Cement circulated.

10-26-92

RECEIVED  
STATE CORPORATION COMMISSION

OCT 20 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2450' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

DATE 11-4-92

INV. NO. 36674

Signed [Signature]  
(TECHNICIAN)