

8-9

1 051338

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,612-0000
NE SW SW, SEC. 22, T. 24 S, R. 15 W/E
990 feet from S section line
4290 feet from E section line
Lease Name McMorran Well # 1
County Stafford 138.13
Well Total Depth 4250 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 272

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company
Name & Address P.O. Box 780167
Wichita, KS 67207

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:15 a.m. Day: 9 Month: 8 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-995-3171

were: 5 1/2" at 4249' with 100 sx cement, Perfs at 4152-56'

1st plug sand back to 4100' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10' sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45 a.m. Day: 9 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 5 sx cement on top of
sand through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Witnessed by Steve Middleton.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1936' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
(could not observe this plugging.)

DATE: AUG 23 1990

Signed Richard W. Lucas
(TECHNICIAN)

INV. NO. 29013

STATE CORPORATION COMMISSION
AUG 14 1990
CONSERVATION DIVISION
WICHITA, KANSAS