

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20687-00-00
Spot: CSWSE Sec/Twnshp/Rge: 22-24S-15W
660 feet from S Section Line, 3300 feet from W Section Line
Lease/Unit Name: CUMMINS Well Number: 1
County: STAFFORD Total Vertical Depth: 4300 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

Conductor Pipe: Size feet: 3139.75
Surface Casing: Size 8.625 feet: 255 WITH 225 SX CMT
Production: Size 4.5 feet: 4299 WITH 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/23/2002 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4140' & 4 SX CMT. 1ST PLUG AT 1025' WITH 50 SX CMT - 10 SX GEL - 100# HULLS. 2ND PLUG AT 290' WITH 50 SX CMT - 100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/23/2002 3:39 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 4198-4214'. ANHYDRITE 1003-1025'. SANDED TO 4155' & 5 SX CMT ON TOP WITH A DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 1025' WITH 10 SX GEL - 100# HULLS - 50 SX CMT. 2ND PLUG AT 290' WITH 100# HULLS - 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
KANSAS CORP COMM
2002 OCT -8 A 11:16

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2022' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 10-10-02
INV. NO. 2003060618

SEP 30 2002

Form SP 247
