

1 090021

10-22

131R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-185-20,546-0000

C NW SW, SEC. 30, T 24 S, R 15 W/E

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lessee Name Loder Well # 1

Operator: F.G. Holl Company

County Stafford 141.37

Name & Address P.O. Box 780167

Well Total Depth 4350 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:40 p.m. Day: 22 Month: 10 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

logs: 4 1/2" at 4349' w/135 sx cement, PBTD 4305', Perfs at 4256-62'

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:55 p.m. Day: 22 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP over perfs with 1 sx hulls and 25 sx cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 100 sx cement.

Maximum pressure 150 psi and shut in 50 psi.

RECEIVED STATE CORPORATION COMMISSION 10-23-90

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2250' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 10-30-90

INV. NO. 29793