

15-095-00384-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., 110 N. Market, Wichita, Ks. 67202

Lease Name Boyle "B" Well No. 1

Location NW NW NE Sec. 34 Twp. 30s Rge. 8 (E) (W) X

County Kingman Total Depth 4399

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Clarke Corporation.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 10 Am. Day 2 Month 1 Year 1980

The above well was plugged as follows:

160' 8 5/8" casing. 5 1/2" casing set at 4305' w/100 sax cement. Pref-  
at 4292' to 4299'-Sand back to 4250'-Top sand w/5 sax mixed cement w/  
dump bailer. Pull 3238' 5 1/2" casing-Set rock bridge at 220'-Dump 4  
yard ready mix cement in 8 5/8" casing to top of casing. Kingman Ready  
Mix Cement Co.

RECEIVED  
STATE CORPORATION COMMISSION

1-4-80  
JAN 4 1980

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-8-80

INV. NO. 1263-w

Signed:   
Well Plugging Supervisor

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company, et al  
Boyle B-1  
LOCATION: NW 1/4 NE, Sec. 34-30-8W, Kingman County, Ks.

Rotary Drilling Commenced 12/18/53  
Rotary Drilling Completed 12/31/53

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 5 Jts of 8 5/8" 2 1/2" J-55 Sals. new casing set at 160' cemented with 150 sacks cement circulated.  
1 1/2 Jts of 5 1/2" 1 1/2" J-55 Sals. new casing set at 130 1/2' cemented with 100 sacks cement.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Red Rock	152
Shale	190
Red Rock & Shale-	910
Salt & shale	1040
Shale & shalls	1350
Lime	2095
Lime & shale	2210
Shale	2430
Shale & shalls	2625
Shale & lime shalls	2750
Shale	2905
Lime & shale	3065
Lime	3813
Lime & shale	3920
Lime	4106
Lime & shale	4210
Lime	4260
Shals & lime	4288
Mississippi Lime	4305 RTD

Circ for samples at 3991  
" " " " 4287  
" " " " 4300  
" " " " 4305  
  
S.L.M. at 3170' O.R.  
S.L.M. at 4111' O.R.  
  
Slope Test at 3170' 0° off  
Slope Test at 4111' 0° off

STATE RECEIVED  
CORPORATION COMMISSION  
NOV 20 1979  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK }

On this 12th day of January, 1954, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 28, 1957

[Signature]  
Notary Public