

15.167.30498.00.00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 117-8 <sup>SE</sup>  
LOCATION C. W. - Mur. - NE  
SEC. 3 TWP. 12 RGE. 15 - W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease C. W. Shaffer

Operator C. K. Carey - Contractor Address Box # 620 McPherson - Kans.

Field \_\_\_\_\_ County Russell

Total Depth 3147 Feet.

Plugging Contractor Morgan Well Plugging Service

Plugging Contractor's License No. 43

Address # 102 W. 18<sup>th</sup> Hutchinson - Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 754 ft. Circulated with cement  
5 1/2 casing set at 3125 ft. 75 sacks of cement  
Plugged back to 3100 ft with sand & rock.  
Drilled 5 sacks of cement at 3100 ft. ripped off  
& pulled the 5 1/2 casing - mud to 250 ft. Set  
rock bridge & 20 sacks of cement at 250 ft.  
Mud to 35 ft. Bridge & 10 sacks of cement  
at the surface.

8-5-53

REL  
STATE CORP

C. N. Stough  
District Conservation Agent

Date 8-1-53

CONSERVATION  
Wichita, Kansas