

15. 167. 00690. 00. 01

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CS 1/2 SE SE

SEC. 21 TWP. 12 RGE. 14W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Heard

Operator Gough W. Davis Address 301 S Clifton Wichita,

Field _____ County Russell

Total Depth 3294 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 254' circulated with cement - 5 1/2" at 3276'
pipe perforated and squeezed by Halliburton Co.
lane-wells plug to 2728', top perforations at 2650', chat to
2640', run 4 sax cement with dump bailer, pulles 2315" 5 1/2",
filled hole with mud to 250', set rock bridge and 15 sax cement,
filled with mud to 40', set rock bridge and 10 sax cement to bottom
cellar.

INDEXED
DIV.

JUL 26 1950 7-26-50

[Signature]
STATE CORPORATION
COMMISSION,
KANSAS.
District Conservation Agent

Date 7-22-50

PLUGGING
FILE SEC 21 T 12 R 14W
BOOK PAGE 18 LINE 23

FL