


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

15-009-151970000

Barton County, Sec. 19 Twp. 16 Rge. 11 (E) W (W)



Locate well correctly on above Section Plat

Location as "NE/CNW%SW%" or footage from lines SW SW NW  
Lease Owner Brunson Drilling Co., Inc.  
Lease Name Redetzke Well No. 5  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6-22-60 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 6-27-60 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3353 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	333'	None
				5-1/2"	3350'	2375'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3350' and found it clear. Sanded hole to 3340' and dumped 5 sacks of cement with dump ~~bailer~~ bailer. Pulled casing and mudded hole to 300'. Bailed hole down and set 10' rock bridge to 290'. Ran 25 sacks of cement, mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1960  
7-18-60  
CONSERVATION DIVISION  
Wichita, Kansas

~~XXXXXXXXXXXXXXXXXXXX~~  
PLUGGING COMPLETED.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 60

My commission expires 5-20-64 Milton J. Voleri Notary Public.



15-009-15197-0000

RECEIVED  
STATE CORPORATION COMMISSION

BRUNSON DRILLING COMPANY, INC.  
Wichita, Kansas

JUN 21 1960

CONSERVATION DIVISION  
Wichita, Kansas

Well: #5 Redetzke

SW SW NW, Section 19-16-11W,  
Barton County, Kansas

COMMENCED RD: 12-10-52  
COMPLETED RD: 12-19-52  
Total Depth : 3353'

Elevation: 1899 DF  
Initial Prod  
Contractor: Pam-Kar Drilg. Co., Inc.

Casing: 333' 8 5/8" OD 24# 8rd thd.  
3350' 5 1/2" OD 14# 8rd thd.

STRATA	DEPTH	TOPS		
Surface soil & clay	20	Hebner	2967	-1066
Rock & shale	60	Toronto	2986	-1085
Shale & sand	85	Douglas	2996	-1095
Shale & shells	240	Brown lime	3060	-1159
Shale & sand	280	Lansing	3076	-1175
Shale	530	Conglomerate	3333	-1432
Redbed & shale	760	Basal sand	3348	-1447
Chalk	764			
Anhydrite	798			
Shale & redbeds	925			
Redbed & shale	1050			
Shale & shells	1475			
Broken lime	1740			
Shale & shells	2765			
Lime & shale	2974			
Lime, sand & shale	3353			
Rotary Total Depth	3353			

*Stop Plug @ 3348  
100 sac cement*

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON DRILLING COMPANY, INC.  
By

*Ralph B. McLaughlin*  
Ralph B. McLaughlin - Sec.-Treas.

Signed and sworn to in my presence this 30th day of December, 1952 by Ralph B. McLaughlin, Secretary-Treasurer of the Brunson Drilling Company, Inc., a corporation in the State of Kansas.

*Edith E. Burrus*  
Notary Public

My commission expires April 25, 1956.