

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15009-151980001
API NUMBER 1-3-53
LEASE NAME Redetzke

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #6 SWD
SPOT LOCATION SW NE NW
SEC. 19 TWP. 16 RGE. 11 (P) or (W)

LEASE OPERATOR OKMAR OIL COMPANY
ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

COUNTY Barton
Date Well Completed 1/3/53

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Plugging Commenced 11/1/85

Character of Well SWD
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Plugging Completed 11/1/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? YES

Producing formation Arbuckle Depth to top 3315' bottom 3317' T.D. 3317'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	353'	none
				5 1/2"	3315'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Spotted 300 sax in 5 1/2" csg--SI overnight w/500# pressure. Cement from 3315' to surface. Pumped 50 sax down annulus between 8 5/8" and 5 1/2"

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Okmar Oil Company License No. 5245
Address Box 723, Hays, Kansas 67601

STATE OF Kansas COUNTY OF Sedgwick, ss.

Melvyn Abels (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Melvyn Abels

(Address) 970 4th Financial Center



SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 85

RECEIVED
Cecelia A. Bowser
STATE COMMISSIONER Notary Public

My Commission expires: August 5, 1987

DEC 11 1985
12-11-85
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4 /-5-
Revised 05-83

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company BRUNSON DRILLING CO., INC.
Farm Redetzke No. 6

SEC. 19 T. 16 N. 11W
SW NE NW

Total Depth. 3315
Comm. 12-21-52 Comp. 1-3-53
Shot or Treated.
Contractor. Pam-Kar Drilling Co.
Issued. 2-28-53

County Barton
KANSAS



CASING:
8 5/8 331'
5 1/2 3313 1/2'

Elevation. 1890 DF

Production. 298 BO, 22% water

Figures Indicate Bottom of Formations.

surface soil & clay	20
rock & shale	50
shale & sand	95
shale & shells	270
shale & sand	305
shale	550
red bed & shale	746
chalk	749
anhydrite	792
shale & red bed	950
shale & shells	1465
broken lime	1835
shale & shells	2708
lime & shale	3005
sand & shale	3037
lime	3042
lime & shale	3315
Total Depth	

TOPS:	
Heebner	2942
Douglas	2971
Brown lime	3035
Lansing KC	3053
Arbuckle	3312

RTD 3314

K. G. S. LIBRARY

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1985

CONSERVATION DIVISION
Wichita, Kansas

BRUNSON DRILLING COMPANY, INC.
Wichita, Kansas

WELL: Redetzke #6

SW NE NW, Sec. 19-16S-11W
Barton County, Kansas

COMMENCED RD: 12-21-53

COMPLETED RD: 1-3-53

ELEVATION: 1890 DF

TOTAL DEPTH: 3314'

CONTRACTOR: Pam-Kar Drlg. Co.

CASING: 331' 8-5/8" OD 24# 8rd thd.
3313 1/2' 5-1/2" OD 14# Csg.

STRATA	DEPTH	TOPS		
Surface soil & Clay	20	Heebner	2942	(-1050)
Rock & Shale	50	Douglas	2971	(-1079)
Shale & Sand	95	Brown Lime	3035	(-1143)
Shale & Shells	270	Lansing-KC	3053	(-1161)
Shale & Sand	305	Arbuckle	3312	(-1420)
Shale	550	Granite Wash	3400	(-1510)
Red Bed & Shale	746			
Chalk	749			
Anhydrite	792			
Shale & Red Bed	950			
Shale & Shells	1465			
Broken Lime	1835			
Shale & Shells	2708			
Lime & Shale	3005			
Sand & Shale	3037			
Lime	3042			
Lime & Shale	3314			
Rotary T. D.	3314			

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1959
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the Daily Drilling Reports.

BRUNSON DRILLING COMPANY, INC.,

By Ralph B. McLaughlin
Ralph B. McLaughlin, Secy-Treas.

Signed and sworn to in my presence this 6th day of January, 1959, by Ralph B. McLaughlin, Secretary-Treasurer, of the Brunson Drilling Company, Inc., a corporation in the State of Kansas.

Mary G. LaFollette
Notary Public
Mary G. LaFollette
STATE CORPORATION COMMISSION

My commission expires ~~January 16, 1959~~
June 16, 1959

RECEIVED
SEP 3 1955
CONSERVATION DIVISION