


OCT 18 1964
15-009-15200000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 19 Twp. 16 Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SW NW
Lease Owner Independent Lease Management Company
Lease Name Redeske Well No. 10
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-3-61 _____ 19____
Plugging completed 10-9-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3315 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	341'	None
				5-1/2"	3312'	1948'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3315', sanded to ~~3300'~~ 3300' and dumped 5 sacks of cement @ 3300' with dump bailer. Pulled 5 1/2" casing. Bailed hole to 300', set 10' rock bridge to 290' and ran 25 sacks of cement @ 290'. Mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1961
10-25-61
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~conservation division~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 1961

My commission expires May 20, 1964
Milton J. Volin Notary Public.



BRUNSON PRODUCTION & EXPLORATION
INC.

15-009-1520000-00

WELL: REDETERE # 10

NE 1/4 NW
SEC. 19-16-11W

COMMENCED RD: 9-20-56
COMPLETED RD: 9-27-56

BARTON COUNTY

TOTAL DEPTH: 3315'

ELEV: 1885 NB

CASING: 341' 8 5/8"
3357.70' 5 1/2" OD

CONTRACTOR:
BRUNSON PRODUCTION
& EXPLORATION, INC.

STRATA	DEPTH		TOPS
Surface, Soil & Rock	20	Topoka	2653- 768
Rock & Shale	40	Reebner	2939-1054
Shale	140	Toronto	2958-1073
Sand & Shale	180	Douglas	2970-1085
Shale	495	Brown Line	3034-1165
Red Beds & Shale	738	Lansing	3050-1165
Anhydrite	773	Arbuckle	3312-1427
Shale	790		
Shale & Redbed	1000		
Shale	1190		
Shale & Salt	1390		
Shale	1430		
Shale & Lime	1485		
Lime & Shale	1673		
Shale & Lime	1868		
Broken Lime	2030		
Lime & Shale	2613		
Lime	2934		
Lime & Arbuckle	3315		
Total Depth	3315		

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1968
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said wells as reflected by the daily drilling reports.

BRUNSON PRODUCTION & EXPLORATION, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin

Signed and sworn to in my presence this 26th day of October, 1956, by Ralph B. McLaughlin-Secretary-Treasurer of the Brunson Production & Exploration, Inc., a Corporation in the State of Kansas.

Donna L. Riley
Notary Public-Donna L. Riley

My commission expires December 31, 1958.