

CP4

State Conservation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

15-009-19180-0000

TYPE OR PRINT
NOTICE: Fill out completely
and return to (Comm. Div.)
office within 30 days
KANSAS CORP CO.

API Number First
Production 9/8/43
LEASE NAME: Redetzke
WELL NUMBER: 2
3960 Ft. From S. Section
Line
1320 Ft From E. Section
Line
SEC. 19 TWP. 16 RNG. 11
WEST
COUNTY Barton
Date Well Completed
September 8, 1943

Plugging Commenced June
21, 1999
Plugging Completed June
21, 1999

OPERATOR: John J. Darrah, Jr.
ADDRESS: 225 N. Market, #300, Wichita, KS 67220
PHONE# (316) 263-2243 OPERATORS LICENSE# 5088
Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

1999 JUL 12 12:51
7-12-99

The plugging proposal was approved on June 19, 1999
by Herb Deines, Hays

KCC District Agent's Name

Is ACO-1 Filed? Unknown see CP-1 If not, is well log attached? TO CP-1
Producing formation Arbuckle Depth to Top 3324 Bottom 3328 T.D. 3328
Show depth and thickness to all water, oil and gas formations

OIL, GAS OR WATER RECORDS		I		CASING RECORD		
Formation	CONTENT	FROM	TO	Size	Put In	Pulled OUT
All between Surface	Water	305	3323	8 5/8	304	3
Casing and Arbuckle	Oil and Water	3324	3328	5 1/2	3324	3

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, If cement or other plugs were used, state the character of same and depth placed, from ft to feet each set.

Allied pumped 225 sacks of 50/40 Pozmix w/ 16 gel and 56# of FloSeal from 2690 back to surface.

Name of plugging contractor D S And W Well Service Llcense No. 6901
Address P.O. Box 231, Claflin, KS 67525-0231
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J.J. Darrah

STATE OF Kansas COUNTY OF Sedgwick, ss.
George P. Stoeppelwerth (Employee of Operator or Operator) of
above-described well, first being duly sworn on oath, says: that I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described
well as filed that the same are true and correct, so help me God.

225 N. Market, Wichita, KS

[Signature] (Signature)
(Address)

SUBSCRIBED AND SWORN TO before me this ninth day of July, 1999

[Signature] Notary Public

My Commission Expires: 9/2/2002



15-009-190030000

15009191800000

WELL NO. 2 LEASE A. A. Redetzke COMPANY'S CONF. COMPANY Gulf Oil Corporation A.F.E. 5585
 DATE—DRILLING BEGAN 8-13-43 WELL COMPLETED 8-6-43 FIRST PRODUCTION 9-3-43
 SAND RECORD Arbuckle lime 3324'-3328' TOTAL DEPTH 3328'
 INITIAL PRODUCTION OIL: "P" 3,000 Barrels on Drawdown test with Sonic Meter
 WATER: 0 Barrels

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	BACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
8-5/8	32	8	C-1	Smls. St. Grade C	304	175	500	-	304
5-1/2	14	8	RT New	Smls. St. Grade H	3325	125	-	-	3325

S-19 T-185 R-11W

C					
NE					
NE					
Barton County, Kansas					

ELEVATION—2165'
RT level with top of 5-1/2" casing

ACIDIZED: 8-6-43 with 2,000 gallons

- (0) - 9 Cellar
- 105 Rock and surface sand
- 510 Shale rock
- 350 Red bed
- 510 Shale and shells
- 530 Sand
- 790 Shale and shells
- 820 Anhydrite
- 840 Shells and anhydrite
- 1020 Shale and shells
- 1225 Red bed and shells
- 1400 Salt
- 1490 Shale and lime
- 1530 Shale and shells
- 1822 Lime, broken
- 1864 Lime and shale
- 1935 Lime
- 1963 Lime, hard
- 2000 Shale
- 2047 Lime
- 2116 Shale and shells
- 2166 Lime and shale
- 2250 Lime, broken
- 2315 Shale
- 2400 Lime and shale
- 2450 Lime, broken
- 2560 Shale
- 2585 Shale and shells
- 2660 Shale
- 2711 Shale and lime
- 3029 Lime
- 3324 Lime and shale
- 3328 Arbuckle lime (total depth)

bn

1500919 003-00-00

