


15009-19242-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County. Sec. 19 Twp. 16 Rge. 11 (E) (W) x
Location as "NE/CNW/SW" or footage from lines. SW SE NW
Lease Owner Okmar Oil Co.
Lease Name Redetzke Well No. #8
Office Address 1130 Vickers KSB&T Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 5-4-72 19____
Application for plugging approved _____ 19____
Plugging commenced 5-15-72 19____
Plugging completed 5-26-72 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3328' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3325'	2609.39'
				8 5/8"	327'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3300'. Mixed and ran 5 sacks cement thru dump bailer.
Plugged with 3 sacks hulls - 20 sacks gel and 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1972
5-31-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26 day of May, 19 72

My commission expires October 1972
D. MILLER
NOTARY PUBLIC
KANSAS

Sidney D. Miller
Notary Public.

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15009-19242-0000

Company- BRUNSON DRILLING COMPANY
Farm- Redetzke No. 8

SEC. 19 T. 16 R. 11W
SW SE NW
330' N of SL, 1230' E of NW/4

Total Depth. 3328
Comm. 10-20-54 Comp. 10-29-54
Shot or Treated.
Contractor. Pam-Kar Drlg. Co.
Issued. 12-4-54

County Barton
KANSAS



Elevation. 1689 KB

Production. 25 BO & NW

CASING:

8 5/8" OD 327'
5 1/2" OD 3325'

Figures indicate Bottom of Formations.

surface soil & clay	10
shale & rock	25
shale & shells	175
hard sand with pyrite	210
shale & shells	285
grey shale	300
blue shale	330
shale	475
sand	505
shale & shells	580
redbed & shale	740
Anhydrite	745
shale	930
shale & salt	1030
shale & shells	1045
broken lime	1605
shale & lime	1840
broken lime	2350
shale & shells	2404
shale & lime	3328
Total depth	

Tops:	
Anhydrite	740
Heebner	2952
Douglas	2980
Brown lime	3044
Lansing	3062

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 - 1972
CONSERVATION DIVISION
Wichita, Kansas