


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-009-19243-0000
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County. Sec. 19 Twp. 16S Rge. EX 11 (W)
Location as "NE/CNW/SW" or footage from lines C W/2 NW NE
Lease Owner Gulf Oil Corporation
Lease Name A. A. Redetzke Well No. 8
Office Address Box 2233, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed February 3, 19 58
Application for plugging filed August 26, 19 58
Application for plugging approved August 29, 19 58
Plugging commenced September 22, 19 58
Plugging completed September 26, 19 58
Reason for abandonment of well or producing formation Well operating below
its economic limit.

If a producing well is abandoned, date of last production September 18, 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation L-KC Depth to top 3073' Bottom 3306' Total Depth of Well 3325' Feet
Show depth and thickness of all water, oil and gas formations. PBTD 3280'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	776'	- 0 -
				5-1/2"	3323'	2458'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with chat from 3280' to 3250' and dumped 5 sacks cement at 3250'.
Filled to 3190'. Mudded hole to 350'. Set rock bridge. Dumped 25 sacks cement
on bridge to 275'. Mudded to 35'. Set Rock bridge and capped with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1958
10-3-58
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Morgan Well Plugging Service
Address 102 W. 18th St., Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas A. Trax (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas A. Trax
Box 2233, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October 19 58

My commission expires 6-3-61

C. C. Lewis
C. C. LEWIS, NOTARY PUBLIC; Notary Public.

PLUGGING
FILE SEC 19 T. 16 R. 11W
BOOK PAGE 126 LINE 17

WELL LOG

15-009-19243-0000

COMPANY Gulf Oil Corporation

SEC. 19 T. 16 R. 11W
LOC. C/W¹/₄NW¹/₄NE¹/₄

FARM A. A. Redetzke NO. 8

TOTAL DEPTH 3328

COMM. 1-20-58


COMP. 1-29-58

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

COUNTY Barton
KANSAS



ELEVATION 1902 K.B.

PRODUCTION

CASING

20 10
15 38 8 5/8 - 776
12 6
13 26 5 1/2 - 3324

FIGURES INDICATE BOTTOM OF FORMATIONS

0-250	Surface Clay & Shale
250-575	Shale & Red Beds
575-690	Shale & Red Beds with sandy streaks
690-757	Shale, Shells, Red Beds
757-785	Anhydrite
785-1235	Shale & Red Beds
1235-1485	Shale
1485-1645	Lime
1645-1960	Lime & Shale
1960-2145	Lime
2145-3325	Lime & Shale
3325	Total Depth

Geologic Tops

Heebner	2958
Toronto	2976
Douglas Shale	2988
Douglas Sand	3008
Brown Lime	3052
Lans/KC	3073
Base/KC	3306
Total Depth	3325

State of Kansas
County of Sedgwick } ss:

PLUGGING
FILE SEC. 19 T. 16 R. 11W
BOOK PAGE 126 LINE 17

I, J. Fred Hambricht of the Lewis Drilling Company

upon oath, state that the above and foregoing is a true and correct copy of the log of the A. A. Redetzke #8 well.

AUG 29 1958

Subscribed and sworn to before me this 29 day of February, 19 58
Wichita, Kansas

My Commission Expires: August 20, 1960

(A. R. Derrington) PUBLIC