

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-192450000
03-14-53

LEASE NAME Redetzke

WELL NUMBER 6

3630 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 19 TWP. 16 RGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed 03-14-53

Plugging Commenced 02-25-97

Plugging Completed 02-25-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John J. Darrah Jr.

ADDRESS 225 North Market, Suite 300, Wichita, Kansas 67202

PHONE (316) 263-2243 OPERATORS LICENSE NO. 5088

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02-25-97 (date)

by District #4 office Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Douglas Depth to Top 2900 Bottom 3000 T.N. 3339

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	773	8 5/8"	773	-0-
	Production	0	3332	5 1/2"	3332	2115'

Describe in detail the manner in which the well was plugged, indicating where the plug fluid was placed and the method or methods used in introducing it into the hole. If cement and other plug were used, state the character of same and depth placed, - from feet to feet. Bottom plug sand and 5 sacks cement to 2850'. Pumped 105 sks 60/40 10% gel, 300# hulls @ 1475', pulled to 800', 40 sks cement, 200# hulls, pulled to 400', spotted 25 sacks cement and 100# hulls, pulled to 200' and circulated cement with 65 sacks. Job completed 3:30 pm.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah

STATE OF Kansas COUNTY OF Barton, ss.

Joseph J. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Joseph J. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1997

Karlyn Beck
Notary Public

My Commission Expires: _____
USE ONLY ONE SIDE OF EACH FORM

 KARLYNN K. BECK
Notary Public - State of Kansas
My Appl. Expires 9-28-98

Form CP-4
Revised 05-88