


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Kingman County. Sec. 33 Twp. 30 Rge. (E) 8 (W)
Location as "NE/CNW/SW" or footage from lines. SE SE NW
Lease Owner Pickrell Drilling Company
Lease Name Tjaden Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/3 19 54
Application for plugging filed 2/3 19 54
Application for plugging approved 2/3 19 54
Plugging commenced 2/3 19 54
Plugging completed 2/3 19 54
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation - - Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Rock		0	160	8 5/8"	160'	None
No oil string was run.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy drilling mud to 160', then 1/2 sack
hulls, plug set with 20 sacks cement. Then
heavy mud to 40' and 1/2 sack hulls, plug
set with 10 sacks cement to bottom of cellar.

*Feed
2-10-54*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth Nat'l Bank Bldg., Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebts*
PICKRELL DRILLING COMPANY
705 Fourth Nat'l Bank, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 19 54

Ethel Zimmerman
Notary Public.

My commission expires January 28, 1957



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 1/19/54
Rotary Drilling Completed 2/3/54

LOCATION: SE SE NW, Sec. 33-30-8W Tjaden #1
Kingman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 5 Jts 160' of 8 5/8" J-55 24# smls casing set at 160'
with 125 sacks bulk cement circulated.

Plugged with heavy drilling mud to 160', then 1/2 sack
hulls, plug set with 20 sacks cement, then heavy mud
to 40' and 1/2 sack hulls, second plug set with 10 sacks
cement to bottom of cellar. O G

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Clay	40	Circ. for samples @ 4323
Red Rock	160	" " " " 4420
Red Bed & shale	815	" " " " 4435
Shale	920	" " " " 4460
Salt & shale	1060	
Shale & shells	1290	
Lime	2065	S.L.M. @ 1885' O.K.
Lime & shale	2365	S.L.M. @ 4448' O.K.
Lime	3014	
Lime & shale	3215	Slope Test @ 1885' 0° off
Lime	3440	Slope Test @ 4448' 0° off
Lime & shale	3540	
Lime	4319	
Mississippi Lime	4460	RTD

The undersigned, C. W. Sebitt, Attorney-in-Fact for PICKRELL DRILLING COMPANY,
hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the
above well as reflected by the Daily Drilling Reports.

PLUGGING
FILE SEC. 33-30-8W
BOOK PAGE 11 LINE 41

PICKRELL DRILLING COMPANY
By [Signature]
Attorney-in-Fact

STATE OF KANSAS
COUNTY OF SEDGWICK

On this 9th day of February, 19 54, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitt, to me known to
be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its
Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and
voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 28, 1957

Notary Public