

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER ¹⁵⁻ 093-21217-0000

LEASE NAME Tysor

WELL NUMBER 7

 Ft. from S Section Line

SE NE SW Ft. from E Section Line

SEC. 22 TWP. 24 RGE. 36 (E) or (W)

COUNTY Kearny

Date Well Completed

Plugging Commenced 10-22-92

Plugging Completed 10-22-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE#(913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-22-92 (date)

by Steve Mildon (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5075

PBTD 5012

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	1588	8 5/8		None
	Casing	0	5074	4 1/2		2472.02'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set
Rig up free point. Casing stuck at 2500'. Free at 2450'. Make to run to shoot off casing. Pull 1 jt. Pump 30 sk. 60/40 6% gel. Pull to 1610' pump 50 sk. 60/40 pull to 800' Pump 40 sk. Pull to 40' pump 10 sk. cement. Circulated. Recovered 78 jt. 4 1/2" tally 2472'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Ellis, ss.

OCT 28 1992

Mr. Ted Crawford

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters hereinafter contained, and the log of the above-described well and that the same are true and correct.

NOTARY PUBLIC
 ROSEMARY SMITH
 My Appt. Exp. 5-1-1995

(Signature) Ted Crawford

(Address) Box 723 Hays, Mo 67601

SUBSCRIBED AND SWORN TO before me this 26 day of October, 19 92

Rosemary Smith
 Notary Public

My Commission Expires: 5-1-1995