

15.185-12116-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 22 Twp. 24S Rge. 15 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines SE NW SE  
Lease Owner D. R. Lauck Oil Company, Inc.  
Lease Name Suiter "C" Well No. 1  
Office Address 301 South Broadway Wichita 2 Kans  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 9-15 1956  
Application for plugging filed 9-15 1956  
Application for plugging approved 9-15 1956  
Plugging commenced 9-15 1956  
Plugging completed 9-15 1956  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production -- 19--  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundedge  
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4221 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		200'	6'	8 5/8"	200'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

hole filled with mud;  
plug and 70 sacks cement squeezed on top to 6' bottom  
of cellar;

9-26-56

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Globe Cementing Company  
Address Great Bend Kans

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
John H. Knightley (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley  
Wichita Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 56  
Elizabeth Kay Notary Public.

My commission expires Sept. 14, 1959

PLUGGING  
FILE SEC. 22 T. 24 R. 15W  
BOOK PAGE 100 LINE 2

D. R. Lauck Oil Company, Inc.

Suiter "C" #1

SE NW SE Sec. 22-24S-15W  
Stafford County, Kansas

Commenced: September 2, 1956  
Completed: September 15, 1956

Casing Record: 200' 8 5/8" cem w/165 sx

Elevation: GR 2022; DF 2025; KB 2027;

Drillers Log

Tops

Sample

sand	145	Heebner	3609-1582
shale & shells	355	Brown Lime	3753-1726
red bed & shells	405	Lansing	3764-1737
sand & red bed	520	Kansas City	4052-2025
red bed & shells	985	Mississippian	4163-2136
Anhydrite	1015	Kinderhook shale	4191-2164
shale & shells	1865	Kinderhook sand	4195-2168
lime & shale	2265	Rotary Total Depth	4221-2194
lime	2370		
lime & shale	3480	DST#1 (M-D) 4165-4175	open 1 hr; with strg blow throughout;
lime	3640		recovered 25' very slightly gas cut mud; all pressures 0#;
lime & shale	3730		
shale	3753	DST#2 (M-d) 4190-4221	open 1 hr with strong decreasing to weak, blow;
lime	4040		recovered 30' mud; all pressures 0#.
lime & shale	4175		
lime & chert	4191		
shale	4195		
sand	4221		
Rotary Total Depth	4221		

D & A

**PLUGGING**  
FILE SEC. 22 T. 24 R. 15W  
BOOK PAGE 100 LINE 2

CONCRETE...  
...  
...