

CM

X

*Recd
12-21-98*

4-110057

D-23,233

API Number: 15-195-21,464 -00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE SE SE SE /4 SEC. 25, 13 S, 21 W
130 feet from S section line
130 feet from E section line

Operator license# 3979

Lease: Bunker SWD Well # 1

Operator: Sally's Tank Service

County: Trego

Address: 1321 Grand Street
Hays, Kansas 67601-9219

Well total depth 1655 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 213 feet

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Sally's Tank Service License# 3979

Address: 1321 Grand Street - Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 18 Month: December Year: 1998

Plugging proposal received from: Rick Gager

Company: Sally's Tank Service Phone: 785-625-8377

Were: According to KCC Rules & Regulations.
Ordered 250 sxs 60/40 pozmix - 10% gel - 700# hulls.
Tie to 5 1/2" casing - pump cement with hulls and pressure up.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 9:30 A.M., Day: 18, Month: December, Year: 1998

Actual plugging report: 8 5/8" set at 213' w/150 sxs cement. 5 1/2' casing at 1649' w/375 sxs cement to surface. Tied to 5 1/2" casing and pumped 200 sxs cement and 700# hulls to Max. P.S.I. 400#. S.I.P. 200#.
Total 200 sxs 60/40 pozmix - 10% gel and 700# hulls.
Anhydrite at 1644'.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES CALC NO Dakota plug: YES NO
Plugged through TUBING CASING Elevation: 2297 GL

I did / did not observe the plugging.

Roger J. Moses
(agent)

101