

3-25-87 291 R

To: 051146  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-22,575-0000  
W/2 NW NW, SEC. 3, T 24 S, R 15 W/E

4620 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3127

Lease Name Cornwell Well # 1-D  
County Stafford 135.59

Operator: E. Equities, Inc.  
Name & Address 8100 East 22nd, N Bldg. 1100  
Wichita, KS 67226-2311

Well Total Depth 4172 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mallard JV, Inc. License Number 4958

Address Box 1009, McPherson, KS 67460

Company to plug at: Hour: 8:15 a.m. Day: 25 Month: 3 Year: 19 89

Plugging proposal received from Kelly Cosby

(company name) Mallard JV, Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 948-56'

1st plug at Arbuckle with 50 sx cement, 2nd plug at 960' with 50 sx cement,

3rd plug at 230' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:00 a.m. Day: 25 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement, 2nd plug at 230' with 40 sx cement, 3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

4-6-89  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 6 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INNOVICE  
did not observe this plugging.

DATE 4-20-89

Signed Richard W. Lacey (TECHNICIAN)

WV. NO. 24397

135-22,575  
15-186-22575-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 10 1989  
month day year

W/2 NW NW Sec 3 Twp 24 S, Rg 15 East  
West

OPERATOR: License # 3127  
Name: E Equities, Inc.  
Address: 8100 E. 22nd, N Bldg 1100  
City/State/Zip: Wichita, KS 67226-2311  
Contact Person: C. E. Dunne  
Phone: 316-684-6508

4620 feet from South line of Section  
4950 feet from East line of Section

(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 4958  
Name: Mallard JV, Inc.

County: Stafford  
Lease Name: Cornwell Well #: 1-D  
Field Name: Macksville

Is this a Prorated Field? yes  no  
Target Formation(s): Arbuckle  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 2020 est. feet HSL

Well Drilled For: Well Class: Type Equipment:  
 Oil  Inj  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OAWO  Disposal  Wildcat  Cable  
 Seismic;  # of Holes

Domestic well within 330 feet: yes  no  
Municipal well within one mile: yes  no  
Depth to bottom of fresh water: 200 180  
Depth to bottom of usable water: 900 180  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 200  
Length of Conductor pipe required: 200  
Projected Total Depth: 4200

If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
 well  farm pond  other

Directional, Deviated or Horizontal wellbore? yes  no  
If yes, total depth location: \_\_\_\_\_

DWR Permit #: unknown  
Will Cores Be Taken?: yes  no  
If yes, proposed zone: \_\_\_\_\_

Spud 3-16-89 3:00 PM pour water  
200' 8 5/8

AFFIDAVIT

PUSHER Kelly Casby  
TD 4172' FORMATION Arb.  
SURFACE PIPE 8 5/8 @ 200'  
ANHYDRITE 948-56' ELEVATION  
STARTING TIME & DATE 8:15 AM 3-25-89  
COMPLETION TIME & DATE 10:00 AM 3-25-89  
1st PLUG @ Arb 50' FT. WI 50 SX  
2nd PLUG @ 960 FT. WI 50 SX  
3rd PLUG @ 230 FT. WI 40 SX  
4th PLUG @ 40 FT. WI 10 SX  
RAT HOLE CIRCULATED WI 15 SX  
MOUSE HOLE CIRCULATED WI 10 SX  
WATER WELL PLUGGED WI \_\_\_\_\_ SX  
CEMENT COMPANY Allied  
TECHNICIAN R.L. D.G.  
60/40poz 6/age/

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 6 1989

CONSERVATION DIVISION  
Wichita, Kansas

5280	1650
4950	1320
4620	990
4290	660
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Wichita, Kansas Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.

15 W