

1080260

TO: STATE CORPORATION COMMISSION

API NUMBER 15-075-20,262-0000
N/2 S/2 SW NE SEC. 4, T 24 S, R 40 W

CONSERVATION DIVISION - PLUGGING SECTION 3150 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BURNETT-GRISSOM WELL # 1-4

TECHNICIAN'S PLUGGING REPORT

COUNTY HAMILTON

OPERATOR LICENSE # 32334

WELL TOTAL DEPTH 2550 ^{82.88} FEET

OPERATOR: CHESAPEAKE OPERATING PRODUCTION CSG: SIZE 4 1/2" @ 2549' WITH 450 SX

NAME AND PO BOX 18496 SURFACE CASING: SIZE 8 5/8" @ 358' WITH 275 SX

ADDRESS OKLAHOMA CITY, OK 73154

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 24 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JOE BROUGHER

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627

WERE: PERFS AT 2443-48

PUMP 5 SX HULLS FOR PLUG AND 150 SX CEMENT. PRESSURE UP BACKSIDE AND PUMP 50 MORE SX IF NEEDED.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:15 PM DAY: 24 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT _____

PUMPED DOWN 4 1/2" CASING 300# HULLS, 130 SX CEMENT. MAXIMUM PSI @ 1000#. SHUT IN AT 500#.

PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 25 SX CEMENT. MAXIMUM PSI @ 300#. SHUT IN WITH 300#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 1 1999

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 9-14-99

SIGNED Kevin D. Strube
(TECHNICIAN)

FORM CP-2/3 (Rev. 11/98)

INV. NO. 60515

2