

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20128-00-00  
Spot: CSWNE Sec/Twnshp/Rge: 3-24S-40W  
1980 feet from N Section Line, 1980 feet from E Section Line  
Lease/Unit Name: GRISSOM Well Number: 1  
County: HAMILTON Total Vertical Depth: 2510 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet: # 81.58  
Surface Casing: Size 8.625 feet: 300 WITH 200 SX CMT  
Production: Size 4.5 feet: 2510 WITH 500 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/20/2001 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 5 SX HULLS FOR PLUG, 150 SX 60/40 POZ-MIX CONTAINING 6% GEL. PRESSURE UP ON; CASING ANNULUS (8-5/8"X4-1/2") & PUMP 50 SX CMT. DOWN ANNULUS, IF NECESSARY.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/20/2001 10:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2501'. PERFS AT 2450-2461'. PUMP 300# HULLS FOR BOTTOM PLUG. PUMP 120 SX CMT TO FILL 4 1/2" CASING FROM BOTTOM TO TOP. PRESSURE TO 1000#. SHUT IN AT 900#. HOOK ONTO BACKSIDE AND PUMP 29 SX CMT. PRESSURE TO 500# AND SHUT IN.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Jim Holland PERT#  
(TECHNICIAN)  
DEC 26 2001

RECEIVED  
DEC 31 2001  
KCC WICHITA

INVOICED  
DATE 01-02-02  
INV. NO. 2002061109

MP

Form 1123