

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-20994-00-00  
Spot: SENENW Sec/Twnshp/Rge: 13-12S-22W  
4422 feet from S Section Line, 2927 feet from E Section Line  
Lease Name: SHERFICK Well #: 2  
County: TREGO Total Vertical Depth: 4053 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 266 N MAIN ST, STE 220  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4048		150 sx
SURF	8.625	327		190 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/15/2016 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: KANSAS CORPORATION COMMIS Phone: (620) 727-3410

Proposed Plugging Method: Ordered 325 sxs 60/40 poz 4% gel cement, 9 sxs gel and 200# hulls  
Dv tool @ 1800' with 425 sxs cement  
Perf's 3610'-3612', 3624'-3626', 3698'-3699', 3706'-3707'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/15/2016 6:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3528' and pumped 9 sx gel follow by 50 sx cement w/100 # hulls.  
Pulled tubing to 1800' and pumped 100 sx cement w/100 # hulls.  
Pulled tubing to 900' and pumped 80 sx cement. Good circulation of cement.  
Pulled tubing out and topped off casing with 15 sx cement.  
Tied on to backside and squeezed with 40 sx cement. Shut in pressure 100 psi.


GPS: 39.01296 -099.71531

Remarks: QUALITY WELL SERVICE TICKET # 6546 SHERFICK FEE FUND PROJECT CONTROL #20140094-002

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

AUG 16 2016

SEP 06 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3