

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21834-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 10-9S-22W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SWAYZE Well #: 1-10
County: GRAHAM Total Vertical Depth: 3921 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3909		125 sx
SURF	8.625	244		200 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KANSAS CORP COMMISSION Phone: (620) 727-3410

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Shot perforations at 2250', 1835', 1050' and 240'.
Open hole.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2016 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3591' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2850' and pumped 100 sx cement. Pulled tubing to 1900' and pumped 230 sx cement. Good circulation of cement. Pulled tubing out. Tied on to backside and pumped 60 sx cement. Shut in pressure 100 psi. Casing and backside full of cement.

GPS: 39.28416 -099.77090

Remarks: QUALITY WELL SERVICE TICKET # 6547 SWAYZE FEE FUND PROJECT CONTROL # 20160016006

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

AUG 26 2016

SEP 06 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3