

5-167-00605-00-00

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Joe K. Brannum of Terrel Drilling & Producing this
 date requested permission to plug the following described well:

Mr. Joe K. Branum guarantees payment of the plugging fee.

Operator's full Name: Terrel Drilling & Producing

Complete Address: Box 273, Russell, Kansas 67665

Lease Name: Beatty Well No. π. 1

Location: SE SW NE Sec. 16 Twp. 12 Rge. 13 (E) (W)

County Russell Total Depth 3160 Oil Well

Gas Well Input Well SWD Well D & AX Lost Hole

Mr. Joe K. Branum was instructed to plug the well as follows:

8 5/8" 157' Gwc.

Filled hole with heavy mud to 300'; set plug with 1/4
sax hulls; displaced 20 sax cement thru drill pipe. Mud
to 150'; set plug with 1/4 sax hulls; displaced 20 sax
cement thru drill pipe. Mud to 40'; 1/2 sax hulls; plug;
displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Joe Trussell
 Conservation Division Agent