

State of Kansas



15-167-08602-000

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 30 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Charle Alyer of Humble Oil & Ref. Co. has this date requested permission to plug the following described well:

Mr. Humble Oil & Refining guarantees payment of the plugging fee.

Operator's full Name: Humble Oil & Refining Company

200 Classen Center-North Building

Complete Address: Oklahoma City, Oklahoma 73106

Lease Name: L. Sellens Well No. # 5

Location: C S/2 N/2SW 1/4 Sec. 17 Twp. 15 Rge. 13 (E)(W)W

County: Russell Total Depth 3075 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. D. B. Pulley was instructed to plug the well as follows:

No surface pipe. Old cable tool hole.

Sanded hole back to 2350' & dumped 5 sax cement with dump bailer.

Circulated hole with mud @ 500'. Pulled pipe to 300' & displaced

50 sax cement thru pipe. Pulled pipe to 60' & displaced 50 sax

cement with Halliburton Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

[Signature]  
 Conservation Division Agent