



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Antares has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Antares Oil Company

Complete Address: 924 Patternson Bldg., Denver, Colorado

Lease Name: Gregory-Tate Well No. 2

Location: SE NW Sec. 33 Twp. 24 Rge. 41 (E) (W)

County: Hamilton Total Depth 2421' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 374' circulated w/ cement. 4 1/2" to 2419' cemented.

Top perforations 2383' Plug bottom w/ 15 sacks cement.

Top of cement 2250' Mud 2250' to 374'

Spot 35 sacks cement 374' to 274' Mud 274' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Conservation Division Agent