



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water) 1
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1965

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Sargent of Livingston Oil Co. has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Livingston Oil Co.

Complete Address: Box 1797 Tulsa, Okla.

Lease Name: Unit 0541 (Owings # 1-15 Well No. 1-15

Location: C SW NE Sec. 5 Twp. 24 Rge. 41 (E) (W)

County Hamilton Total Depth 2315' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8"-405' Circulated w/cement. 4 1/2"-2315' Cemented. Top perforations-2240'

Plug bottom w/20 Sax.cement top cement 2000' Mud 2000' to 700'

Spotted 10 Sax.cement 700' to 600' Mud 600' to 60'

Plug, Hulls, 5 Sax.cement 60' to 0

Very truly yours,

[Signature]
Conservation Division Agent