

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

SEP 24 1965

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Anadarko Production Co.Complete Address: Box 351 Liberal, KansasLease Name Millsap Well No. # A-1Location SE NE NW Sec. 6 Twp. 24 Rge. 41 EX (W)County Hamilton Total Depth 2304'Abandoned Oil Well Gas Well X Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Sargent Casing Pulling ServiceAddress: Liberal, Kansas License No. 511Operation Completed: Hour 3 PM Day 22 Month 9 Year 65

The Above well was plugged as follows:

10 3/4"-661' Circulated w/cement. 4 1/2"-2302' Circulated w/cement.2 3/8"-1121' Cemented. Top Perforations 859'Plug bottom w/10 Sax.cement top cement 2100'. Mud 2100' to 700'Spotted 10 Sax.cement 700' to 600' Mud 600' to 54'Plug, 5 Sax.cement 54' to 0 No pipe pulled. Company Pump.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 9/27/65INV. NO. 1859-4Signed: [Signature]
Well Plugging Supervisor