

15.167.20690.00.00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name J. L. King Oil Operations

Complete Address Drawer 73, Russell, Kansas 67665

Lease Name Kepka XX Well No. # 1

Location NW NE SE Sec. 29 Twp. 14 Rge. 12 (E) (W) W

County Russell Total Depth 3180

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 128, Ellinwood, Kansas License No. # 462

Operation Completed: Hour 9:30 A.M. Day 7 Month 11 Year 1974

The above well was plugged as follows:

8 5/8" csg. 615' Cwc. Perf. 2173'

Sanded hole back to 2140' & dumped 5 sax cement with dump bailer. Pulled pipe.

Mud to 375', set 25' rock bridge, & displaced 5 yds. Ready-mix Cement, cementing

from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/11/74

INV. NO. 273-W

Signed: [Signature]
Well Plugging Supervisor