

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20375-00-00
Spot: NWNENE Sec/Twnshp/Rge: 18-32S-8E
5201 feet from S Section Line, 913 feet from E Section Line
Lease Name: WALKER Well #: 1
County: COWLEY Total Vertical Depth: 1955 feet

Operator License No.: 34798
Op Name: VIKING PRODUCTION LLC
Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1954		25 SX
SURF	7	47		40 SXS CMT
SURF	7	407		40 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/18/2016 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Rcvd. from: BERT CARLSON Company: _____ Phone: (620) 485-6064

Proposed
Plugging
Method:

Plug per KCC Direction

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 07/27/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/ TBG @ 1870', SNYDER CEMENTING MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1446'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 500'-501' (2 HOLES), WELL WOULD NOT CIRCULATE. RIH ON WIRELINE CUT CASING @ 350', LAYED DOWN 11 JOINTS 4-1/2" CASING. RIH W/TBG @345', SNYDER CEMENTING MIXED & PUMPED 90 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED.

Top	Bot	Thru	Comments
1922	1927		

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Form CP-2/3

JK
AUG 31 2016