



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 4 1963

CONSERVATION DIVISION
 Wichita, Kansas

3-4-63

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co., Inc. has this

date requested permission to plug the following described well:

Mr. C. W. Shaffer guarantees payment of the plugging fee.

Operator's full Name: E. E. McGully & C. W. Shaffer

Complete Address: Russell, Kansas

Lease Name: McGully Well No. #.2

Location: W/2 SW SE Sec. 6 Twp. 13 Rge. 14(E) (W)

County Russell Total Depth 3258 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" 382' Cwc.

Filled hole with heavy mud to 380'; set plug with hulls;
displaced 30 sax cement thru drill pipe with Sun Cementing
Company's pump truck. Mud to 40'; 1/2 sax hulls; plug;
displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman
 Conservation Division Agent