

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

MAY 4 1964

CONSERVATION DIVISION
 Wichita, Kansas

5-4-64

Dear Sir:

Mr. Jackson of Earl Wakefield has this
 date requested permission to plug the following described well:

Mr. Jackson guarantees payment of the plugging fee.

Operator's full Name: Earl Wakefield

Complete Address: 515 Union Center, Wichita, Kansas

Lease Name: Barnett Well No. # 1

Location: C NE SW Sec. 34 Twp. 24 Rge. (E) (W) 42

County Hamilton Total Depth 2470 Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Jackson was instructed to plug the well as follows:

8 5/8"-113' Circulated w/cement.

Mud 2470' to 732' Spotted 25 Sav. cement 732' to 644'

Mud 644' to 124' Spotted 15 Sav. cement 124' to 74'

Mud 74' to 28' Plug, Halls, 10 Sav. cement 28' to 0

Very truly yours,

[Signature]
 Conservation Division Agent