



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
December 19 81

DEC - 8 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

12-8-81

15-047-20,972-0000

Dear Sir:

Mr. James Shruiner of Sterling Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: F. G. Holl

Complete Address: 427 East Kellogg Wichita, Kansas 67207

Lease Name: Wilson Well No. 3-8

Location: 330' F5L-1320' FEL of NE 1/4 Sec. 8 Twp. 24S Rge. 17W (E) (W)

County: Edwards Total Depth: 4510'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Shruiner was instructed to plug the well as follows:

There is 254' of 8 5/8" surface casing cemented with 210 lbs of cement. The anhydrite was from 1169' to 1189'. The cedar hill was at 800'. 1st plug at 1160' with 50 lbs of cement. 2nd plug on solid bridge at 840' with 50 lbs of cement. 3rd plug pushed rubber plug to 240' with 25 lbs of cement on top of it. 4th plug at 40' to 0' with 10 lbs of cement on solid bridge. They pumped 5 lbs of cement in rat hole + 2 lbs of cement in water well.

Very truly yours,

Paul Lutter
Conservation Division Agent