

State of Kansas



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 5 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Dean Sharpe of Barnett Oil Co. has this  
 date requested permission to plug the following described well:

Mr. Sharpe guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Co.

Complete Address: 411 1st National Bank Bldg., Wichita, Kansas

Lease Name: Garner Well No. # 1

Location: NW NE NW Sec. 12 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 3896 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sharpe was instructed to plug the well as follows:

260' of 8 5/8" surface pipe, cemented with 250 sacks.  
Fill hole with mud to 250', 1st cementing plug, 1/4 sack  
hulls, cement with 20 sacks. Fill hole with mud to 40',  
2nd cementing plug, 1/4 sack hulls, cement with 10 sacks  
to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent